FacilityCheckList 8/17/06 11:45:47 AM

SOS Facility Check List

 \bullet \square Systems run hot!!!!!

□ Exhibit Area
 □ Projectors, sphere, and computer
 □ Footprint See diagram. Generally need 30' x 30' square area
 □ Projectors go at the corners of the square
 ■ NC (Network Control) computer is generally near by
• □ Power
 ■ 3.5 AMPS of power at each projector location. UPS mounted near projector
• □ Audio
 ■ Four speakers mounted on ceiling near projector
 ■ Need lockable cabinet for Network Control computer (NC)
■ Light levels
 Look for direct lighting, big windows that will shine on the sphere
☐ General power requirements for whole system
 □ Each computer needs 3 AMPS
 ■ Each projector needs 3.5 AMPS
 ■ Few amps for other pieces
□ Cable and Conduit Runs
 ■ Video cables go from display computer to each projector
 □ Please estimate distance from computer room to projectors
 ■ Each projector needs power/UPS
 ■ Audio speakers need power
 ■ One CAT6 cable run from computer room to NC computer
 ■ Please estimate distance for this CAT 6 run
 ■ Audio cable from NC to speakers
□ Computer room
• Space
 ¬ NC (Network Control computer) - Location needs to be "near" sphere for remote control to work. This computer should be near exhibit
 □ Four display computers + one spare shelf space for five (5) Dell mid-towers
• □ Power
 ■ Each computer uses up to 300 - 400 watts (2000) watts for five
 ■ All systems are on a UPS
 ■ Generally, need two 20-AMP circuits
 □ Cooling (very important!)
 □ Require adequate cooling via A/C and proper air flow around the systems

1